


BRUHAT BANGALORE MAHANAGARA PALIKE

SCHEDULE - B

Name of work: Estimate for Improvements to Roads and Drains at Kogilu Lake Road in Ward No.5 Byatarayanapura Sub Division

Sl. No.	Approved Qty.	Description	Unit	Schedule-B Rates	
				KRIDL	
				In Figures	In Words
1	464.88	KSRRB 300 Excavation for road formation KSRRB 300-3. Earth work excavation and foming in embankment by manual means in ordinary soil with initial lead upto 15m, and lift of 1.5m, (when earth ls taken from bank cutting of from borrow pits) including breaking of clods, spreading to required line and level, forming, and cost of all labour complete as per specifications. (excluding watering and compaction of earth) MORTH chapter 3. No. 141/ Item No. 19.3/ PWD SR 2015-16	cum	105.84	Rupees One Hundred Five and Eighty Four Paise Only
2	160.92	KSRRB 300-1. Earth work excavation by manual means in Hard Soil soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications.MORTH chapter 3. No. 141/ Item No. 19.2/ PWD SR 2015-16	Cum	115.56	Rupees One Hundred Fifteen and Fifty Six Paise Only
3	160.92	KSRRB M400-7: Construction of granular sub base by providing coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per specifications.	Sqm	1490.40	Rupees One Thousand Four Hundred Ninety and Forty Paise Only
4	677.95	KSRRB M300-53 : Construction of embankment with approved material Gravel/Murum with all lifts and leads, trasnporting to site, spreading, grading to required slope and compacting to meet requirement Table 300-2 complete as per specifications (which includes cost of gravel / murum, watering charges & compaction by vibratory roller) MORTH Specification No. 305. (Page No. 144 & Item No. 19.60) PWD SR 2015--16	Cum	311.04	Rupees Three Hundred Eleven and Four Paise Only
5	387.40	KSRRB M400-17: Providing, laying spreading and compacting graded stones aggregate to wet mix macadam specifications including premixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying, in uniform layers with paver in sub base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH specification NO. 406, No. 154/ Item No. 20.18/ PWD SR 2015-16	Cum	1713.96	Rupees One Thousand Seven Hundred Thirteen and Ninety Six Paise Only
6	1937.00	KSRRB 500-4: providing and applying primer coat from 7.5 to 9.8 kg and 9.8 to 12.2kg per 10 sqm for surfaces of low and medium porosity respectively over prepared surface of granular base with cut bank M.C-70 or any other bitumen mixed with diesel at 10 kg per 10 sqm heated in bitumen boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM of machineries complete as per specificationsDo- Medium Porosity MORTH chapter 5, No. 157/ Item No. 21.5/ PWD SR 2015-16	Sqm	59.40	Rupees Fifty Nine and Forty Paise Only



 21/11/16

Sl. No.	Approved Qty.	Description	Unit	Schedule-B Rates	
				KRIDL	
				In Figures	In Words
7	48.43	KSRRB M500-18: Providing and laying semi dense bituminous concrete 25mm thick with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder at 4.5 to 5% of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem roller to achieve the desired compaction as per MORTH specifications clause No. 500.8 complete in all respects as per specifications. P. No. 159/ Item No. 21.20.1/ PWD SR 2015-16	Cum	9264.24	Rupees Nine Thousand Two Hundred Sixty Four and Twenty Four Paise Only
8	625.80	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means including loading and unloading. From 0.00 to 2.00 Km (Page No.123,	Cum	67.32	Rupees Sixty Seven and Thirty Two Paise Only


 EXECUTIVE ENGINEER-4
 KRIDL, BBMP DIVISION
 BENGALURU-560 010


 Executive Engineer,
 Byarayanapura Division
 BBMP, Bangalore - 92

25/11/14